



UNIVERSITY OF THE PHILIPPINES MANILA
Campus Planning, Development and Maintenance Office
Padre Faura St. Ermita, Manila 1000, Philippines
Tel: (632) 525 2233 • (632) 526 8420 • (632) 814 1258 • (632) 814 1257



PROJECT : PROPOSED RENOVATION OF CEILING, ROOFING & LEDGES
LOCATION : College of Nursing
University of the Philippines Manila
SUBJECT : BIDFORM

ITEM	DESCRIPTION	QTY.	UNIT	UNIT COST	TOTAL COST
1.00	GENERAL REQUIREMENTS				
1.10	Mobilization and Demobilization	1.00	lot		
1.20	Scaffolding, warehouse, board ups, canvass/temporary covering and safety signages	1.00	lot		
1.30	Health and Safety (PPE, Medkit, Medical check-up/testing as required for new normal etc.)	1.00	lot		
	TOTAL GEN REQ'TS			Php	
2.00	ARCHITECTURAL WORKS				
2.10	Ceilings Works				
	Dismantling of existing ceiling				
	600mm x 600mm x 4.5mm thick Fiber cement board on T-runner complete with hangers and supports painted finish				
	Sub-total			Php	
2.20	Painting Works				
	Soft Slab including surface preparation				
	Sub-total			Php	
2.30	Repair of Ledges				
	Construction of weephole				
	Repair/Restoration of roof corner including supply and installation of aluminum sieve and accessories				
	Application of flexible cementitious waterproofing at ledges concrete gutter, water tank area, etc including surface preparation				
	Concrete topping (25mm) slope to drain with chicken wire				
	Sub-total			Php	
2.40	Restoration Works				
	Restoration of underslab, delapidated roof sheets, banded accessories and other affected area				
	Declogging of Roof drain and restoration of affected area				
	Sub-total			Php	
	TOTAL ARCHITECTURAL			Php	

note 7:00
15 SEP 2020
15 SEP 2020

ITEM	DESCRIPTION	QTY.	UNIT	UNIT COST	TOTAL COST
3.00	ELECTRICAL WORKS				
	3.5 mm ² THHN wire				
	20mm dia PVC pipe				
	Flourescent lamp fixture (1200 mm x 300 mm) recessed type with aluminum reflector complete with 2 bulbs direct wired LED flourecent tube 16W T8				
	Restoration of electrical wiring				
	TOTAL ELECTRICAL			Php	

*****SUMMARY*****

1.00 GENERAL REQUIREMENTS
2.00 ARCHITECTURAL WORKS
3.00 ELECTRICAL WORKS

PhP _____
PhP _____
PhP _____

TOTAL PROJECT COST

PhP _____

Amount in Words : _____

Note: Bonds & Securities and power & water supply consumption are considered as overhead expenses while Plans (As-built plan) is considered as miscellaneous expense which are already included in the computation of OCM (mark-up).

See DPWH Department Order No 197

By the act of submitting this bid, I/we hereby confirm that I/we:

- have inspected the site
- determined the characteristics of the contract works and the conditions for this project
- examined all instructions, forms, terms and project requirements in the Bidding Documents
- was/were given the opportunity to submit queries at least ten(10) calendar days before the submission of bids
- have examined and agreed to the correctness of the Bill of Quantities

Submitted by:

Name and Signature:

Company Name:

Position:

Date: