

PURCHASE REQUEST
UP Manila - Philippine General Hospital

Department : **Ophthalmology & Visual Sciences-SOJR**
 Section : _____ SAI No.: _____ I 04/27/17
PUR17-08-1131 ALOBS No. _____ Date: _____

Item No.	Unit	Item Description	Qty.	Unit Cost	Total Cost
		Supply and Installation of Closed Circuit Television Video (CCTV) Surveillance System and Viewing Station (to cover all floors of SOJR)			
		Digital Video Recorder with the following specifications	4		
		• high definition DVR 16 channel embedded Linux			
		• full channel with at least 720p resolution			
		• HDMI and VGA output			
		• support up to 16 channels with synchronous playback			
		• 4TB Video Grade Storage 1 year warranty swap onstock			
		• 32 Kbps to 6 Mbps Video Bitrate			
		Camera and Power Supply	54		
		• high definition cameras			
		• at least 2.0 megapixels			
		• at least 720p resolution			
		• turret or dome shape			
		• enough in number to cover significant floor area of the building			
		Viewing Station			
		• construction of glass-enclosed viewing station at the space identified at SOJR			
<i>8-32</i> TOTAL					600,000.00

Purpose : For Sentro Oftalmologico Jose Rizal Building Security and Surveillance

Requested by: <i>Mari Valbuena</i> MARISSA N. VALBUENA, M.D. Chair	Date 4/27/17	Certified Funds Available <i>Ruby D. Allado</i> RUBY D. ALLADO Chief, Budget Division	Date
Recommended by: ORIGINAL SIGNATURE MARIA ANTONIA E. HABANA, M.D. Deputy Director for Health Operations <i>APR 27 2017</i>	Date	Approved <i>Gerardo B. Legaspi</i> GERARDO B. LEGASPI, M.D. Director <i>AUG 15 2017</i>	Date

PURCHASE REQUEST
UP Manila - Philippine General Hospital

Department : **Ophthalmology & Visual Sciences-SOJR**
 Section : _____ SAI No.: _____ I Date: 04/27/17
 PUR17-08-1131 ALOBS No. _____ Date:

Item No.	Unit	Item Description	Qty.	Unit Cost	Total Cost
		Supply and Installation of Closed Circuit Television Video (CCTV) Surveillance System and Viewing Station			
		(to cover all floors of SOJR)			
		Integration Materials			
		• Cat6 cable pure copper wire; equivalent or better			
		• total length should cover all cameras			
		• video active Balun connector and power			
		LED Monitor	4		
		• at least 21 inch monitor display, diagonal			
		Integration Works			
		• cable pulling, roughings, homeruns for coaxial, electrical			
		• testing and commissioning			
		• wires should be placed discretely so as not to disrupt current building design and architecture			
		Warranty and Service			
		• 2 year warranty parts and service			
		• on call service; readily available technicians			
		(Please charge to SOJR Trust Fund 439-191)			
		8-72	TOTAL		600,000.00

Fund 184
 439 - 2040101000 - 191 SOJR
 8/1/17

Purpose : For-Sentro Oftalmologico Jose Rizal Building Security and Surveillance

Requested by: <i>Mari Valbuena</i> MARISSA N. VALBUENA, M.D. Chair	Date 4/27/17	Certified Funds Available <i>Ruby D. Allado</i> RUBY D. ALLADO Chief, Budget Division	Date
Recommended by: ORIGINAL SIGNED MARIA ANTONIA E. HABANA, M.D. Deputy Director for Health Operations	Date APR 27 2017	Approved <i>Gerardo D. Legaspi</i> GERARDO D. LEGASPI, M.D. Director	Date AUG 15 2017